
20,98442,720





Forklift pockets 4 x 8 44" outside


Porcelain wall hung fixtures Stainless Steel napkin dispenser. Soap disp. & mirror Rubber coin over epoxy steel flooring Jets CVS Toilets and greywater injector Vacuum shut off and water valves Ducted ventilation Obscure skylights in radius doors Vandal resistant pebble finished wall panels Double foil radiant barrier insulation Led 50,000 hr LED lighting with aux. 12 volt inlet/outlet Automatic body sensing lighting and occupancy indicator All metal and composite construction

Forklift pockets all sides 4 ISO bottom corners

- 3"camlock female vacuum connection
- 1 1.25" camlock female water connections

Optional Hose and duct connection kit available


This document is the property of and contains unpublished proprietary information and trade secrets of A.M.S. Global Inc. By accepting possession of the document the recipient agrees to make no copies transcriptions or any use of this document or the information contained herein except as authorized by A.M.S. Global Inc.and further agrees to safe keep this document and return in to A.M.S. Global Inc. upon demand.





(A) 78"x24" RH

48"x24" RH CDS 8 ADA 1ST

80"x 36" RH








Handrails

Top Height 36" above Platform

Top of Cross Bars 14"below bottom of Top Rail. Railing 1.5" OD Diameter and slides into 4" piece of 1.5" ID pipe welded to landing.



These restrooms are designed to be compliant with all current guidelines as we are aware of . Many guidelines have gray areas and points open to interpretation. Different entities may have differed interpretations or local differences. We suggest getting approvals of final plans from the authorities in the local the unit will be placed



