
20,98442,720



Porcelain wall hung fixtures & mirrors
Rubber coin over epoxy steel flooring
Jets CVS Toilets and greywater injector
On demand electric heated water
1 ADA shower and bench
Vacuum shut off and water valves
Ducted ventilation Obscure skylights in radius doors
Vandal resistant pebble finished wall panels
Double foil radiant barrier insulation
Led 50,000 hr LED lighting with aux. 12 volt inlet/outlet
Automatic body sensing lighting and occupancy indicator
All metal and composite construction
Forklift pockets all sides

- 4 ISO bottom corners
- 1 Cam Lock pipe female vacuum connection
- 1 Cam Lock female water connections

Optional Hose and duct connection kit available

This document is the property of and contains unpublished proprietary information and trade secrets of A.M.S. Global Inc. By accepting possession of the document the recipient agrees to make no copies transcriptions or any use of this document or the information contained herein except as authorized by A.M.S. Global Inc. and further agrees to safe keep this document and return in to A.M.S. Global Inc. upon demand.


Forklift pockets 4 x 8 44" outside


Approved by




SK 8 ADA 1STS


- (A) 78"x24" RH
- (B) 48"x24" RH
- © 80"x 36" RH








7'-4"



Handrails

Top Height 36" above Platform

Top of Cross Bars 14"below bottom of Top Rail. Railing 1.5" OD Diameter and slides into 4" piece of 1.5" ID pipe welded to landing.



These restrooms are designed to be compliant with all current guidelines as we are aware of . Many guidelines have gray areas and points open to interpretation. Different entities may have differed interpretations or local differences. We suggest getting approvals of final plans from the authorities in the local the unit will be placed



